


CONSTRUCTION OF CCGI SHED FOR STAFF VEHICLE PARKING
(SIZE- L-140, W- 15 , H- 10)FT

SPECIFICATIONS

1. By manual Laying and dig of 1.5 x1.5 x2.5 ft (L x W x Deep) hole of the casting and fixing of the base frame made up of 45x45x6 Angle and fixing of 10 mm base plate on it of size of 120x120 mm then fill it with the cement, sand and 40mm Aggregate (1:3:4).
2. For Pillar 75 x75x 3.2 mm round pipe for Truss and purling 40x40x2.9 mm pipe will be fixed, top of pillar and truss must be weld with 8mm plate.
3. CCGI sheet will be fix on it with SS fastners.
4. Structure must be treated with anti-corrosion red oxide (2 Coats) and black Paint will be apply.
5. Pillar to pillar gape 8 ft
6. Quote your rates per sq ft

Note: - Quote your rate including Labour, transportation, installation and all taxes like GST etc. Visit the site / place before quoting your bid.

Principal 
Army Public School
Janglor (J&K)