

**CCGI SHED FOR PARENTS NEAR TUCK SHOP (SIZE- L-36, W- 35 , H- 15)FT**

**SPECIFICATIONS**

1. By manual Laying and dig of 1.5 x1.5 x2.5 ft (LxWxDeep) hole of the casting and fixing of the base frame made up of 45x45x6 Angle and fixing of 10 mm base plate on it of size of 120x120 mm then fill it with the cement, sand and 40mm Aggregate ( 1:3:4 ).
2. For Pillar 100 x100x 3.2 mm round pipe for Truss and purling 80x40x2.9 pipe will be fixed, Top of pillar and truss must be weld with 8mm plate.
3. CCGI sheet will be fixed on it with SS fastners.
4. Structure must be treated with anti-corrosion red oxide (2 Coats) and black Paint will be applied.
5. Pillar to pillar gape not more than 10 ft
6. Quote your rates per sq ft

**Note: - Quote your rate including Labour, transportation, installation and all taxes like GST etc. Visit the site / place before quoting your bid.**

Principal   
Army Public School  
Janglor (J&K)